



The 16<sup>th</sup> National Conference on Building Commissioning

# **“PFTs: Useful Tool or A Complete Waste of My Time?”**

Gretchen Coleman, EEI





**“PFTs: Useful Tool or A Complete Waste of My Time?”**

**Definition**

A prefunctional test checklist is a detailed list of Installation, Operational, and Documentation requirements that need to occur or be submitted before a piece of equipment or system can be functionally tested.

**New Industry Standard Term**  
**Construction Checklists**



## **“PFTs: Useful Tool or A Complete Waste of My Time?”**

### **Purpose of the PFT**

The commissioning prefunctional test checklist has many purposes. It is the responsibility of the contractors to provide operating building systems within the guidelines of the contract. The PFTs are one tool that helps the contractors fulfill that responsibility.

- Indicates that systems are ready for functional testing. Answers the question “what does complete mean?”
- Reduces the amount of time the CxA spends functionally testing.
- Allows the information reported by the DDC system to be used for testing purposes.
- Delineates for the contractor what is required in the specifications.
- Reduces the chance of contractor backcharges due to systems not being ready when CxA arrives to conduct functional testing.
- Saves money for everyone!



**“PFTs: Useful Tool or A Complete Waste of My Time?”**

How are they supposed to be used?

Each subcontractor, mechanical, electrical, test and balance, controls has a part to play in any HVAC system. One way to use them is to provide a checklist for each subcontractor. The idea is for each subcontractor to use the list as they are installing and starting up the piece of equipment to assure themselves that they have not forgotten a task.



## “PFTs: Useful Tool or A Complete Waste of My Time?”

Examples of Problems that PFTs are designed to Eliminate

- Vibration isolation components in the shipping position instead of the operating position
- Fans running backwards
- Overcurrent protection devices the wrong size
- Missing gauges
- Valves stroking the wrong direction or slipping on the actuator rods
- Setpoints not input.

The PFT will help the contractor eliminate issues such as these, which is their responsibility, instead of relying on the CxA team to develop a punchlist for them.



## **“PFTs: Useful Tool or A Complete Waste of My Time?”**

How can the PFT process be improved?

- Stronger specification language, include sample PFTs in the specifications, reference Cx in all pertinent sections.
- Put in the specifications that back charges will apply if the CA arrives on site and the equipment is not ready (eliminate coffee shop PFTs)
- Put submission of PFT documentation as a milestone on the CPM schedule.
- Easier to use forms.
- Forms for each individual piece of equipment instead of for each type of equipment.
- Adhering the PFT on the piece of equipment and let each contractor sign off as he completes his tasks – one PFT for each unit, probably multiple pages



The 16<sup>th</sup> National Conference on Building Commissioning



**“PFTs: Useful Tool or A Complete Waste of My Time?”**

How can PFT documentation be  
Improved?

Lets look at some samples:




# The 16<sup>th</sup> National Conference on Building Commissioning



## “PFTs: Useful Tool or A Complete Waste of My Time?”

Construction Checklist				
	Ready		Date	Initials
	Yes	No		
<b>A. General</b>				
1. Unit clean & free from dirt & debris				
2. Lockers installed and sealed				
3. Chain falls, spacers as needed				
4. Safety devices (lift screens, warning labels)				
5. Access doors present & closed				
6. Components accessible				
7. Thermal insulation				
8. Insulating oil/moisture				
9. Roof coils				
10. Balancing devices, valves				
11. Balancing devices, dampers				
12. Vibration isolation				
13. Condensate pan				
14. Proper condensate trap clearance				
15. Flare/Gas				
16. Best orientation (for membranes, gaskets, etc.)				
<b>B. Controls</b>				
1. Distribution and/or delay				
2. Air flow and direction				
3. Field wiring				
4. Control wiring connections and flow				
5. Valves open or set				
6. Air leaks or steam traps				
7. TAB devices				
<b>C. Piping</b>				
1. Electrical service and connections				
2. Spacers & disconnects/valves				
3. Scale				
4. Bulk guard				
5. Safe valves				
6. VFDs				
7. Airlocks/interlocks				
8. Rotation				



Comments:



# The 16<sup>th</sup> National Conference on Building Commissioning



## “PFTs: Useful Tool or A Complete Waste of My Time?”



PROJECT NAME

M-PFT-XXX

Mechanical Contractor Pre-functional Test Checklist

Equipment: Rooftop Unit  
 Location: \_\_\_\_\_  
 Serves: \_\_\_\_\_

Mark: \_\_\_\_\_  
 Date: \_\_\_\_\_  
 Company: \_\_\_\_\_  
 Technician: \_\_\_\_\_

Check when complete

Notes, completion data:

Components and installation per project documents and approved submittals:

- Fans \_\_\_\_\_
- Motors \_\_\_\_\_
- Belts \_\_\_\_\_
- Safety devices (inlet screens, belt guards) \_\_\_\_\_
- Cabinet or built-up plenum \_\_\_\_\_
- Coils \_\_\_\_\_
- Condensate drain pan and piping \_\_\_\_\_
- Filter bank (w/clean operational filters) \_\_\_\_\_
- Humidifier \_\_\_\_\_
- Volume control devices (variable frequency drive, inlet vanes, inlet cones) \_\_\_\_\_
- Control dampers (outside air, return air, exhaust, relief, isolation, barometric) \_\_\_\_\_
- Control valves \_\_\_\_\_
- Balancing devices (valves and dampers) \_\_\_\_\_
- Vibration isolation (in operating position) \_\_\_\_\_
- Instrumentation (thermometers, pressure gauges, magnahelic, P/Ts) \_\_\_\_\_
- Thermal insulation \_\_\_\_\_
- Equipment device tags and labels \_\_\_\_\_
- Access panels, doors and lights \_\_\_\_\_
- Blenders \_\_\_\_\_
- Roof curb \_\_\_\_\_

Operational checks complete:

- Fan/motor alignment \_\_\_\_\_
- Fan/motor lubrication \_\_\_\_\_
- Fan rotation \_\_\_\_\_
- No unusual vibrations or noises \_\_\_\_\_
- Acceptable air leakage \_\_\_\_\_
- Debris removed and surfaces clean \_\_\_\_\_
- Manufacturer's start-up test complete \_\_\_\_\_

Documentation complete:

- Operation and maintenance information \_\_\_\_\_
- Manufacturer's test report submitted (attach copy) \_\_\_\_\_
- Contractor's start-up report submitted (attach copy) \_\_\_\_\_
- As-built drawings current \_\_\_\_\_

Checklist Complete

Signature \_\_\_\_\_

Date \_\_\_\_\_



E-PFT-XXX

PROJECT NAME

Electrical Contractor Pre-functional Test Checklist

Equipment: Rooftop Unit  
 Location: \_\_\_\_\_  
 Serves: \_\_\_\_\_

Mark: \_\_\_\_\_  
 Date: \_\_\_\_\_  
 Company: \_\_\_\_\_  
 Technician: \_\_\_\_\_

Check when complete

Notes, completion data:

Components and installation per project documents and approved submittals:

- Conduit \_\_\_\_\_
- Wiring \_\_\_\_\_
- Variable frequency drive \_\_\_\_\_
- Motors \_\_\_\_\_
- Starters \_\_\_\_\_
- Disconnects \_\_\_\_\_
- Over-current protection devices \_\_\_\_\_
- Switches (HOA, push-button, selector, safety) \_\_\_\_\_
- Hardware interlocks \_\_\_\_\_
- Control transformers \_\_\_\_\_
- Convenience outlets \_\_\_\_\_
- Lighting \_\_\_\_\_
- Grounding \_\_\_\_\_
- Wiring tags and equipment labels \_\_\_\_\_

Operational checks complete:

- Motor amps/volts \_\_\_\_\_
- Motor rotation \_\_\_\_\_
- VFD enclosure fan and filter \_\_\_\_\_
- Circuits tested \_\_\_\_\_

Documentation complete:

- Operation and maintenance information \_\_\_\_\_
- Contractor's test report submitted \_\_\_\_\_
- As-built drawings current \_\_\_\_\_

Checklist Complete

Signature \_\_\_\_\_

Date \_\_\_\_\_





# The 16<sup>th</sup> National Conference on Building Commissioning



## “PFTs: Useful Tool or A Complete Waste of My Time?”



PP-XXX

PROJECT NAME

Controls Point to Point Checklist

Equipment: Rooftop Unit  
 Location: \_\_\_\_\_  
 Serves: \_\_\_\_\_

Mark: \_\_\_\_\_  
 Date: \_\_\_\_\_  
 Company: \_\_\_\_\_  
 Technician: \_\_\_\_\_

Check when complete

Temperature Sensors:

- Discharge Air
- Mixed Air
- Outside Air
- Return Air
- Preheat Air

Point Name	Point Type	Open Circuit Reading

Notes:

\_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

Humidity Sensors:

- Outside Air
- Return Air

Point Name	Point Type	Open Circuit Reading

\_\_\_\_\_  
 \_\_\_\_\_

Pressure Sensors:

- Discharge Space

Point Name	Point Type	Open Circuit Reading

\_\_\_\_\_  
 \_\_\_\_\_

Airflow Stations:

- Supply
- Return

Point Name	Point Type	Open Circuit Reading

\_\_\_\_\_  
 \_\_\_\_\_

Current Sensors:

- Supply Fan
- Return Fan

Point Name	Point Type	Open Circuit Reading

\_\_\_\_\_  
 \_\_\_\_\_

Stand Alone Devices:

- Freezestat
- Discharge Pressure Filter

Point Name	Point Type	Open Circuit Reading

\_\_\_\_\_  
 \_\_\_\_\_



CC-XXX

PROJECT NAME

Controls Calibration Checklist

Equipment: Rooftop Unit  
 Location: \_\_\_\_\_  
 Serves: \_\_\_\_\_

Mark: \_\_\_\_\_  
 Date: \_\_\_\_\_  
 Company: \_\_\_\_\_  
 Technician: \_\_\_\_\_

Check when complete

Temperature Sensors:

- Discharge Air
- Mixed Air
- Outside Air
- Return Air
- Preheat Air

Point Name	BMS	Measured	Correction Factor

Notes:

\_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

Humidity Sensors:

- Outside Air
- Return Air

Point Name	BMS	Measured	Correction Factor

\_\_\_\_\_  
 \_\_\_\_\_

Pressure Sensors:

- Discharge Space

Point Name	BMS	Measured	Correction Factor

\_\_\_\_\_  
 \_\_\_\_\_

Airflow Stations:

- Supply
- Return

Point Name	BMS	Measured	Correction Factor

\_\_\_\_\_  
 \_\_\_\_\_

Current Sensors:

- Supply Fan
- Return Fan

Point Name	Amp Reading	Fan Speed	Correction Factor

\_\_\_\_\_  
 \_\_\_\_\_

Stand Alone Devices:

- Freezestat
- Discharge Pressure Filter

Point Name	Design	Measured	Adjustment Made

\_\_\_\_\_  
 \_\_\_\_\_

Dampers:

- Outside Air
- Min Outside Air
- Return Air
- Exhaust Air

Point Name	Millamp, Voltage, or Pressure		Correction Factor
	Full Closed	Full Open	

\_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_





## **“PFTs: Useful Tool or A Complete Waste of My Time?”**

How can PFT documentation be Improved?

One idea is to have 3 “Pre-Functional Test” forms per contractor.

- The first would be an installation checklist with a one-line diagram.
- The second would cover startup information and include submission of manufacturer’s startup sheets.
- The third would cover information required before the CxA comes out to start functional testing and would include:
  - O&M Manuals
  - Control Point to Point and Control Calibration sheets
  - Preliminary TAB reports
  - Duct Pressure Tests
  - Piping Pressure Tests
  - Acknowledgement that all resources and tools will be available when the CxA reaches the job (the right contractors with the right tools).



**“PFTs: Useful Tool or A Complete Waste of My Time?”**

3 “Pre-Functional Test” forms (con’t)

Submission of the first would signal start-up activities are ready to commence.

Submission of the second and third would signal functional testing is ready to commence.



**“PFTs: Useful Tool or A Complete Waste of My Time?”**

- Is this an improvement?
- Would it make life easier for owners and the contractors?
- Is it cost effective?
- Different ideas?



**“PFTs: Useful Tool or A Complete Waste of My Time?”**

- Contractor’s Opinion – are CxA provided PFTs of any use? Are they viewed as just more paperwork? Do they aid in keeping a project on schedule? Is there a better way to format them?
- Owner’s Opinion - are the PFTs cost affective? Do you see them as a benefit? Are you willing to pay the CxA to more closely monitor their use in the field?
- Provider’s Opinion – are you successful in getting real PFTs with meaningful information? Do you find that even though the PFTs are meticulously filled out they are not a good representation of field conditions?
- Final questions – are they worth it? If so, how can the process and documentation be improved?