




**New San Francisco Federal
Building Site Tour**

Mark Levi, GSA - Owner
Tim Christ, Morphosis - Design Team
**Jonathan Soper, Enovity - Commissioning
Authority**


NCBC April 2006






Mark Levi
GSA PBS Pacific Rim Region
New Building Efficiency

NCBC April 2006



The Problem

- New courthouses underperforming courthouses from the 1960s or early 1970s in energy performance
- Performance is worst soon after completion
- Significant operational problems at time of occupancy




▶ Evo DeConcini U.S. Courthouse, Tucson, AZ




▶ Walsh Courthouse, Tucson, AZ





AVERAGE TOTAL ENERGY CONSUMPTION (BTUs/GSF)
TUCSON, AZ (1 of 2)


















Size Comparison

Location	Total Building Area (GSF)	
	OLD Courthouse	NEW Courthouse
TUCSON	82,360 GSF	413,000 GSF
LAS VEGAS	201,203 GSF	454,885 GSF
SACRAMENTO	368,112 GSF	773,987 GSF

- The Suspects**
- Less shading, more clear glazing
 - Less thermal mass
 - DDC controls
 - Construction QA / QC problems
 - Lack of design integration (e.g. controls sequences; responsibility for envelope performance)

Systemic Design Problems

- Over-design (over-estimated loads + safety factors, not understanding load diversity)
- Not distinguishing infrastructure (worst case sizing) from programming
- Inability to handle low loads, small 24/7 loads
- Failure to fully specify sequences of operations
- Lack of systemic integration of disciplines



Systemic Construction Process Problems

- TAB quality problems
- DDC controls (programming & hardware)
- Poor envelope construction (missing insulation, leaks, holes)
- Poor ductwork installation
- No QA/QC of lighting controls (responsibility not well defined)
- Poor as-built documentation (if any)



DDC Controls – A Serious Mess

- Minimal specifications (or specs from OEM)
- No adherence to specifications
- Incomplete programming (e.g., schedules not set up, factory defaults not changed)
- Low quality LANs, workstations
- Poor skills by techs (sometimes)
- Poorly defined sequences of operation
- Process designed to fail – installer too far down food chain, too late in process, no communication with owner/designers



Solutions (SFFB)


- Commissioning
- Rigorous specifications (esp. BAS)
- Design features to make up for glazing
- Aggressive review of BAS programming
- More integration of envelope with systems
- More O&M preparation before turn-over




Tim Christ, Morphosis
Design Team


NCBC April 2006





















What about comfort inside?



- ASHRAE Standard 55 “specifies conditions or comfort zones here 80% of sedentary or slightly active persons find the environment thermally acceptable.”
- Based on fully air-conditioned test box laboratory tests. Results very well represent what people accept when they have no personal control over central AC.
- But what about naturally ventilated buildings around the world??

Natural ventilation comfort range superimposed on outdoor air graph



- Need internal pickup of less than 7°F


Proving the concept. . . .





Berkeley Lab



- Department of Energy software development
- Integration of COMIS and EnergyPlus (replacement of DOE2)
- Most commercially available software cannot model the dynamic heat transfer for thermal mass simultaneous to the bulk air flow for natural ventilation.








Windward people open windows . . .




- Computational Fluid Dynamics shows upward macro flow




Refining the details. . . .

- Modification of window mullion/flap to direct air across NW occupied zone



Window extrusion shaped to enhance occupant feedback

- Flow deflector for bottom of user-operable window – directs main jet into occupied region



Control System Principles


- Group windows together
- Closed, half-open or fully-opened positions
- 10 opening modes
- The windward and leeward sides are identified
- Temperatures, and external pressures measured
- Each half of each floor is independently controlled
- The system responds to these variables by changing the Mode value by ± 1

Windward – mostly user control


Leeward – building control system



Sensor Map



Schematic representation of the aperture modes





- Each floor of the building is divided into two symmetrical sides.
- The black square in the center of the figures is an elevator/service core that creates a significant obstruction to cross-ventilation airflow.



Jonathan Soper
Enovity, Inc.
Commissioning Authority


NCBC April 2006





Project Status

- All major electrical and HVAC equipment installed
- Building almost 100% enclosed and sealed
- Power to main distribution panels, no water
- Controls hardware and wiring 60% complete
- Equipment start-up likely begin in June
- Functional testing in late summer
- Completion and move in late 2006



Building Owner
General Services Administration

Energy Efficient Design of Mechanical Systems by Arup

- Underfloor air distribution for air handlers serving lower floors of Tower
- Waterside economizers for heat pumps serving Tower cabins
- Primary variable flow CHW and HW distribution
- VFDs on water cooled centrifugal chillers
- Innovative sequences of operation



Scope of Commissioning Services

- LEED project with additional commissioning
- Systems to be commissioned include: HVAC and plumbing systems, BAS, natural ventilation system, lighting controls
- More focused testing on under floor air distribution systems



Commissioning Approach

- Focus on submittal reviews pertaining to control systems
- Focus on early review of control sequences programming
- Pre-functional tests will use contractor forms as basis
- Cooperation with controls contractor for functional testing
- Post occupancy tests to rely on long term trend data



Wrap Up

Successful commissioning will require:

- Early identification of potential system deficiencies
- Good cooperation and effective communication between owner, design team, contractor, construction manager and commissioning authority